

Specifications

Dutch
Quality

Real Meadow 45

Application	Landscape, garden lawns, roofgardens, infrastructure	
Pile material	PE + PP	
Production method	Tufted - 3/8"	
Primary backing	100 % PP with fibre-lock fleece	
Secondary backing	SBR Latex	
Stitches	17.850 /m ²	± 10%
Pile height	45 mm	± 10%
Total height	47 mm	± 10%
Pile weight	1.545 gr/m ²	± 10%
Total weight	2.465 gr/m ²	± 10%
Infill	Silica sand, gradation 0.5 - 1.0 mm, minimal 80% round of shape	
Advice	8-10 kg/m ²	
Uv stability	> 6.000 hours	
Product guarantee	10 years	
Water permeability	60 liter/min/m ²	
Rol length	25 m ¹	

AGN Grass®

Real products | Real prices